Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Project Division

Name of Work: Improvements to DWCC in Ward No. 08 and other SWM works in KodigehalliImprovements to DWCC in Ward No. 08 and other SWM works in Kodigehalli

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	DWCC Building:								
1	KSRRB 200-9 Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of thorney jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications. MORTH / Chapter 2(P.No 136, I.No.18.12 of PW,P&IWTD S.R 2017-17)								
	Basic rate	9.00							
	11% AD-HOC	0.99							
	Sub Total-1	9.99							
	6% AW	0.60							
	Sub Total-2	10.59							
	Building Area	1	12.00	12.00		144.00	Sqm	10.59	1525.00
2	KSRB 2-1.1: Earthwork in surface excavation in **ordinary soil** for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeeding 50 m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. Specification No KBS 2.1(a)/2.3.1 (P.No 5, I.No.2.1 of PW,P&IWTD S.R 2017-17)								
	Basic rate	157.00							
	21% AD-HOC	32.97							
	Sub Total-1	189.97							
	6% AW	11.40							
	Sub Total-2	201.37							
	10.00km Lead, Lift Transport	100.00							
	Sub Total	301.37							
	Building Area	1	12.00	12.00	0.90	129.60	Cum	301.37	39057.00
3	KSRB 2-2.1: Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in **ordinary soil** not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m, after breaking of clods complete as per specifications. Specification No.KBS 2.1(a)/2.3.5. (P.No.5, I.No.2.3 of PW,P&IWTD S.R 2016-17)								
	Basic rate	189.00							
	21% AD-HOC	39.69							
	Sub Total-1	228.69							
	6% AW	13.72							
	Sub Total-2	242.41							
	10.00km Lead, Lift Transport	100.00							
	Sub Total	342.41							
	Column Footing								
	F1	8	1.50	1.50	1.00	18.00			
	F2	2	1.20	1.20	1.00	2.88			
						20.88			
	Wall Foundation								
	long wall	2	10.00	0.75	0.60	9.00			
	Short wall	2	6.00	0.75	0.60	5.40			
	partition	2	4.50	0.75	0.60	4.05			
						18.45			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	For sump	1	2.00	2.00	2.00	8.00			
	Deduction	4	1.50	0.75	0.60	2.70			
		2	1.20	0.75	0.60	1.08			
						3.78			
					Net qty	43.55			
	Consider 60% of the qnty	--	--	--	--	26.13			
						26.13	**Cum**	**342.41**	**8947.00**
4	KSRB 2-2.2: Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m.and above in width, in **hard soil** not exceeding 1.5m.in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. Specification No.KBS 2.1(a)/2.3.5. (P.No.5, I.No.2.4 of PW,P&IWTD S.R 2016-17)								
	Basic rate	283.00							
	21% AD-HOC	59.43							
	Sub Total-1	342.43							
	6% AW	20.55							
	Sub Total-2	362.98							
	10.00km Lead, Lift Transport	100.00							
	Sub Total	462.98							
	Consider 40% of the Quantity of Item No 2	--	--	--	--	17.42			
						17.42	**Cum**	**462.98**	**8065.00**
5	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix M 7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No.4.3 of PW,P&IWTD S.R 2016-17)								
	Basic rate	4867.00							
	21% AD-HOC	1022.07							
	Sub Total-1	5889.07							
	6% AW	353.34							
	Sub Total-2	6242.41							
	Column Footing								
	F1	8	1.50	1.50	0.15	2.70			
	F2	2	1.20	1.20	0.15	0.43			
						3.13			
	Wall Foundation								
	long wall	2	10.00	0.75	0.15	2.25			
	Short wall	2	6.00	0.75	0.15	1.35			
	partition	2	4.50	0.75	0.15	1.01			
						4.61			
	For Flooring								
		1	10.00	6.00	0.150	9.00			
	Outside platform	2	14.00	3.00	0.150	12.60			
		2	6.00	2.00	0.150	3.60			
	For sump	1	2.00	2.00	0.15	0.60			
	Deduction	4	1.50	0.75	0.10	0.45			
		2	1.20	0.75	0.10	0.18			
						0.63			
						3.98			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
				total qty		4.36			
						4.36	**Cum**	**6242.41**	**27229.00**
6	KSRB - 5.2.3: Providing and constructing granite size stone masonry in foundation cement mortar 1:6, stone hammerd dressed in courses not lss than 20 cms high, bond stones at two m.apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13. (P.No.23, I.No.5.6 of PW, P&IWTD SR 2016-17)								
	Basic rate	4187.00							
	21% AD-HOC	879.27							
	Sub Total-1	5066.27							
	6% AW	303.98							
	Sub Total-2	5370.25							
	Wall Foundation								
	long wall	2	10.00	0.60	0.60	7.20			
	Short wall	2	6.00	0.60	0.60	4.32			
	partition	2	4.50	0.60	0.60	3.24			
						14.76			
						14.76	**Cum**	**5370.25**	**79265.00**
7	KSRB - 5.3.3: Providing and constructing grantie / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.No.23, I.No.5.9 of PW, P&IWTD SR 2016-17)								
	Basic rate	5005.00							
	11% AD-HOC	550.55							
	Sub Total-1	5555.55							
	6% AW	333.33							
	Sub Total-2	5888.88							
	Wall Foundation								
	long wall	2	10.00	0.45	0.40	3.60			
	Short wall	2	6.00	0.45	0.40	2.16			
	partition	2	4.50	0.45	0.40	1.62			
						7.38			
	For Flagging Course								
	Shanthivana layout								
	3rd cross	1	174.00	0.45	0.45	35.24			
		1	180.90	0.45	0.23	18.72			
	4th cross	1	283.80	0.45	0.45	57.47			
		1	74.20	0.45	0.23	7.68			
	Amco Layout - 1st main								
	2nd cross	1	76.80	0.45	0.45	15.55			
		1	76.00	0.45	0.23	7.87			
	3rd cross	1	64.00	0.45	0.45	12.96			
		1	75.00	0.45	0.23	7.76			
	4th cross	1	90.80	0.45	0.45	18.39			
		1	33.00	0.45	0.23	3.42			
	16th cross CQAL Layout	1	345.00	0.45	0.45	69.86			
		1	54.50	0.45	0.23	5.64			
	8th main, 16th cross	1	130.50	0.45	0.45	26.43			
		1	64.80	0.45	0.23	6.71			
	4th cross Road	1	302.00	0.45	0.23	31.26			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
						339.70	Cum	5888.88	2000475.05
8	KSRB 4.1.6: Providing and laying in position plain cement concrete of mix M-15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates at 0.78cum and fine aggregates at 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation, plinth and cills including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2. (P.No 12 I.No 4.6 of PW,P&IWTD SR 2016-17)								
	Basic rate	5441.00							
	21% AD HOC	1142.61							
	Sub Total-1	6583.61							
	6% AW	395.02							
	Sub Total-2	6978.63							
	For cills								
	W	4	1.80	0.20	0.10	0.14			
	coping								
	long wall	2	10.00	0.45	0.10	0.90			
	Short wall	2	6.00	0.45	0.10	0.54			
	partition	2	4.50	0.45	0.10	0.41			
	For compound	2	12.00	0.45	0.10	1.08			
		2	12.00	0.45	0.10	1.08			
	For sump	1	2.00	2.00	0.10	0.40			
						4.55			
						4.55	Cum	6978.63	31746.00
9	KSRB 4.6.1: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.No.15, I.No.4.28 of PW,P&IWTD SR 2016-17)								
	Basic rate	231.00							
	21% AD-HOC	48.51							
	Sub Total-1	279.51							
	6% AW	16.77							
	Sub Total-2	296.28							
	Column Footing								
	F1 No = 4	32	1.50	--	0.45	21.60			
	F2 No = 2	8	1.20	--	0.45	4.32			
						25.92	Sqm	296.28	7680.00
10	KSRB - 4.6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.No.15, I.No.4.31 of PW, P&IWTD SR 2016-17)								
	Basic rate	293.00							
	21% AD-HOC	61.53							
	Sub Total-1	354.53							
	6% AW	21.27							
	Sub Total-2	375.80							
	Plinth beam								
	Long wall	4	10.00	--	0.30	12.00			
	Short wall	4	6.00	--	0.30	7.20			
		4	4.50	--	0.30	5.40			
						24.60	Sqm	375.80	9245.00

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
11	KSRB 4-6.5: Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. Specification No. KBS 4 6.2. (P.No.16, I.No 4.32 of PW,P&IWTD SR 2016-17)								
	Basic rate	366.00							
	21% AD-HOC	76.86							
	Sub Total-1	442.86							
	6% AW	26.57							
	Sub Total-2	469.43							
	Columns upto Foundation-Ground level								
	C1 (0.20+0.45=0.65)	16	0.60	--	1.05	10.08			
	C2 (0.20+0.20=0.40)	4	0.40	--	1.05	1.68			
	Columns above ground up to GF								
	C1 (0.20+0.45=0.65)	16	0.60	--	3.20	30.72			
	C2 (0.20+0.20=0.40)	4	0.40	--	3.20	5.12			
	For sump	1	2.00	2.00	--	4.00			
	for rest room	1	1.50	1.20	--	1.80			
						53.40	**Sqm**	**469.43**	**25068.00**
12	KSRB 4-6.7: Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides and soffits of beams, beam haunchings, cantilever, girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.No.16, I.No.4.34 of PW,P&IWTD SR 2016-17)								
	Basic rate	256.00							
	21% AD-HOC	53.76							
	Sub Total-1	309.76							
	6% AW	18.59							
	Sub Total-2	328.35							
	Lintel Beam								
	Long wall	2	10.00	--	0.15	3.00			
	Short wall	2	6.00	--	0.15	1.80			
						4.80	**Sqm**	**328.35**	**1576.00**
13	KSRB - 4.2.8: Providing and laying in position reinforced cement concrete of design mix M 20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for R.C.C beams, columns of all sizes in foundation plinth and superstructure ground floor level for roof slabs, staircase, lintels, columns, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Speceification No. KBS 4.1,4.6. (P.No.14, I.No 4.13 of PW, P&IWTD S.R 2016-17)								
	Basic rate	6158.00							
	21% AD-HOC	1293.18							
	Sub Total-1	7451.18							
	6% AW	447.07							
	Sub Total-2	7898.25							
	Column Footing								
	F1	8	1.50	1.50	0.45	8.10			
	F2	2	1.20	1.20	0.45	1.30			
						9.40			
	Plinth beam								
	Long wall	2	10.00	0.20	0.30	1.20			
	Short wall	2	6.00	0.20	0.30	0.72			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
						1.92			
	Columns upto Foundation- GF level								
	C1 (0.23+0.45)	8	0.20	0.40	1.05	0.67			
	C2 (0.23+0.23)	2	0.20	0.20	1.05	0.08			
						0.76			
	Columns ABOVE GROUND level								
	C1 (0.2+0.60)	8	0.20	0.40	1.20	2.05			
	C2 (0.2+0.45)	2	0.20	0.20	1.20	0.26			
						3.82			
	Lintel								
	Long wall	2	10.00	0.20	0.15	0.60			
	Short wall	2	6.00	0.20	0.15	0.36			
						0.96			
	Outside platform	2	14.00	2.00	0.125	7.00			
		2	6.00	2.00	0.125	3.00			
						10.00			
	For sump	1	2.00	2.00	0.15	0.60			
	for rest room	1	1.50	1.20	0.15	0.27			
					Net Qty	27.72			
						27.72	Cum	7898.25	218924.00
14	KSRB 4.2.10: Providing and laying in position reinforced cement concrete of design mix M 20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @ 0.5175cum and fine aggregates @ 0.345cum, with superplastisiser @ 0.225lts machine mixed, well compacted for plain chajja of 7.5cms average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. Specification No.KBS 4.1, 4.6. (P.No.14, I.No.4.19 of PW,P&IWTD SR 2016-17)								
	Basic rate	456.00							
	21% AD-HOC	95.76							
	Sub Total-1	551.76							
	6% AW	33.11							
	Sub Total-2	584.87							
	Chajja								
		4	1.50	--	0.45	2.70			
		1	3.00	--	0.45	1.35			
						4.05	Sqm	584.87	2369.00
15	KSRB - 4.9.2: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 (P.No.17, I.No.4.46 of PW, P&IWTD SR 2016-17) (Rate As per Quarter rate issued by the PWD on 01-07-2017)								
	Basic rate	60607.00							
	21% AD-HOC	12727.47							
	Sub Total-1	73334.47							
	6% AW	4400.07							
	Sub Total-2	77734.54							
			Qty	Per Kg		Total Qty in tonne			
	Ground Floor								
	Footing		9.40	80.00		0.75			
	Plinth Beam		1.92	80.00		0.15			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Columns		3.82	120.00		0.46			
	Lintels		0.96	60.00		0.06			
	Chejja		4.05	30.00		0.12			
	For Sump		0.60	60.00		0.04			
	for rest room		0.27	100.00		0.03			
						1.61			
						1.61	**Tonne**	**77734.54**	**124787.00**
16	KSRB 5-14: Providing and constructing Precast concrete solid blocks with compressive strenght not less than 35Kg/sqm with cement mortar 1:4 masonry (quion, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms confirming to IS 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing etc., complete as per specifications. (P.No.25, I.No.5.27.1 of PW,P&IWTD SR 2016-17)								
	Basic rate	937.00							
	21% AD-HOC	196.77							
	Sub Total-1	1133.77							
	6% AW	68.03							
	Sub Total-2	1201.80							
	Long wall	2	10.00	--	3.20	64.00			
	Short Wall	2	4.30	--	3.20	27.52			
	Partition wall	2	4.50	--	2.40	21.60			
						113.12			
	For sump	4	2.00	--	2.00	**16.00**			
	for rest room	1	1.80	--	2.40	**4.32**			
	Deduction								
	W	4	1.50	--	1.20	7.20			
	D1	1	2.40	--	2.10	5.04			
	Gate	1	5.00	--	2.40	12.00			
						24.24			
					Net Qty	109.20			
						109.20	**Cum**	**1201.80**	**131236.00**
17	KSRB 15-3.9: Providing 18mm thick cement plaster in single coat with cement mortor 1:6, to brick masonry including rounding off corners wherver required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(P.No.114, I.No.15.17 of PW,P&IWTD SR 2016-17)								
	Basic rate	198.00							
	21% AD-HOC	41.58							
	Sub Total-1	239.58							
	6% AW	14.37							
	Sub Total-2	253.95							
	External wall plastering								
	Long wall	2	10.00	--	3.20	64.00			
	Short Wall	2	6.00	--	3.20	38.40			
						102.40			
	For sump	4	2.00	--	2.00	**16.00**			
	Deduction	Coff							
	W	0.50	4	1.50	1.20	3.60			
	D	0.50	1	2.40	2.10	2.52			
	Gate	2	5.00	--	2.40	24.00			

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
						10.12			
					Net Qty	88.82			
						98.94	Sqm	253.55	24613.00
18	Water proofing the inside surface of tanks (OHT & UGT) applying of modified polymers soft acrylic water coat @0.40 kg/sqm in 2 coats including all labour charges tools and equipments, all complete as per the specification (P No 67, I No 10 5 3 of PW P&IWTD SR 2016-17)								
	Basic rate	285.00							
	21% AD HOC	59.85							
	Sub Total 1	344.85							
	6% AW	20.69							
	Sub Total 2	365.54							
	For sump wall	4	2.00		2.00	16.00			
		1	2.00	2.00		4.00			
					Net Qty	20.00			
						20.00	Sqm	365.54	7311.00
19	KSRB 15 3 3 Providing 12mm thick cement plaster in single coat with cement mortar 1:6 to brick masonry including rounding off corners wherver required smooth rendering. Providing and removing scaffolding including cost of materials, labour, curing complete as per specifications (P No 113, I No 15 11of PW P&IWTD SR 2016-17)								
	Basic rate	150.00							
	21% AD HOC	31.50							
	Sub Total 1	181.50							
	6% AW	10.89							
	Sub Total 2	192.39							
	Internal wall plastering								
	LONG WALL	2	10.00	-	3.20	64.00			
	SHORT WALL	2	5.60	-	3.20	35.84			
	Partition wall	4	4.50	-	2.40	43.20			
	for rest room	2	1.80		2.40	8.64			
						151.68			
	Deduction	Coff							
	W	0.50	4	1.50	1.20	3.60			
	D	0.50	1	2.40	2.10	2.52			
						6.12			
					Net Qty	145.56			
						145.56	Sqm	192.39	28004.00
20	KSRB - 15 7: Providing lime rendering for plastering to wall and ceiling including cost of materials, labour, curing complete as per specifications (P.No.115, I No.15 33 of PW P&IWTD SR 2016-17)								
	Basic rate	25.00							
	21% AD HOC	5.25							
	Sub Total 1	30.25							
	6% AW	1.82							
	Sub Total 2	32.07							
	Quantity same as Internal Plastering		-	-	-	145.56	Sqm	32.07	4667.00
21	KSRB 15 16 1 Providing and finishing external walls in two coats with water proof cement paint of approved brand and shade to give and even shade after throughly brooming the surface to remove all dirt and loose powdered material free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications (with primer) (P No 118, I No 15.53.2 of PW P&IWTD SR 2016-17)								
	Basic rate	84.00							

Scanned by CamScanner

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	21% AD-HOC	17.64							
	Sub Total-1	101.64							
	6% AW	6.10							
	Sub Total-2	107.74							
	Quantity same as External Plastering	--	--	--	--	96.92	Sqm	107.74	10442.00
22	KSRB 15-15.1: Providing and applying painting in two coats with plastic emulsion paint of approved brand and shade on wall surface to give an even approved shade after throughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. (With primer) (P.No.117, I.No.15.51.2 of PW,P&IWTD SR 2016-17)								
	Basic rate	90.00							
	21% AD-HOC	18.90							
	Sub Total-1	108.90							
	6% AW	6.53							
	Sub Total-2	115.43							
	Quantity same as Internal Plastering	--	--	--	--	145.56	Sqm	115.43	16803.00
23	KSRB 14.7-2 : Providing and laying red oxide flooring 40 mm thick, with an under layer of 30mm thick M-15 cement concrete, using broken granite metal of 12.5mm nominal size and top layer of 10mm thick plaster with 1:3 cement mortar mixed with red oxide (using 3.5 kg of red oxide per 50 kg of cement) finished with floating coat of neat cement mixed with red oxide (mix of same proportion) , including cost of materials, labour, curing, complete as per specifications. Specification No. KBS 14.3 (P.No.102, I.No.14.9. of PW,P&IWTD SR 2012-17)								
	Basic rate	578.00							
	21% AD-HOC	121.38							
	Sub Total-1	699.38							
	6% AW	41.96							
	Sub Total-2	741.34							
	inside	1	9.60	5.60	--	53.76			
						53.76	Sqm	741.34	39855.00
24	KSRB - 7.9: Providing and fixing M.S.grill work for windows and ventilators weighing 21 kg/sqm using M.S. flats, or M.S.square rods, or combination of M.S.flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifictions. Specification No. KBS 7.12 (P.No.32, I.No.7.9 of PW, P&IWTD SR 2016-17)								
	Basic rate	78.00							
	21% AD-HOC	16.38							
	Sub Total-1	94.38							
	6% AW	5.66							
	Sub Total-2	100.04							
	W	4	1.50	--	1.20	7.20			
						7.20			
	Consider weight 21kg/sqm	--	--	--	--	151.20	Kgs	100.04	15126.00
25	KSRB 15-18.2: Providing and applying enamel metal paint two coats (Excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materails, labour, complete as per specifications.(P.No.121 I.No.15.74 of PW, P&IWTD S.R 2016-								
	Basic rate	82.00							
	21% AD-HOC	17.22							
	Sub Total-1	99.22							
	6% AW	5.95							

Scanned by CamScanner